TENDER FORM.

To

The Chief Commandant,
Mysore State Troops, Bangalore.

I/We offer to supply the article according to the sealed sample at the Military Stores at the rates given in the accompanying list. It will be delivered at the Military Stores within one month from the date of communication of acceptance of tender.

Currency notes to the value of Rs. 50 are here in enclosed as earnest money.

Dated Yours faithfully,

TUMKUR DISTRICT.

Notice dated 25th February 1920.

Notice is hereby given that sealed tenders will be received at the Office of the Deputy Commissioner, Tumkur District, up to 15th March 1920, for restoring Mattikere tank, Registered No. 95 of Gubbi Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1920.

2. The plans, detailed estimate and conditions may be seen at the Deputy Commissioner's Office at Tumkur, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Deputy Commissioner. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one hundred (Rs. 100) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the Mattikere tank, Registered No. 95, Gubbi Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Deputy Commissioner, who does not bind himself to accept the lowest or any tender, or to assign any reason, whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Deputy Commissioner's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for restoring Mattikere minor tank, Registered No. 95, Gubbi Taluk.

Items of work	Per	Quantity
Bund at R. L. 55·00, top width 6 feet.—		
1. Earthwork to bund including watering and tamping	C. yd.	29·02
2. Turfing	S. yd.	46·13
3. Removing and resetting old rough stone work	C. yd.	196
4. Rongh stone work, new	"	753
5. Providing and fixing new grade stones with figuring and painting	Each	24
6. Do benchmark stones	"	2
7. Do registered number stones	"	1
8. Jungle clearing	Lump sum	
Sluice No. 1 at R. L. 43·50.—		
1. Earthwork cutting and refixing	C. yd.	150
2. Burnt brick in surki mortar	C. ft.	632
3. Burnt stone slabs dressed 6" thick	S. ft.	111
4. Plastering with surki mortar	Sq.	2·96
5. Providing plug and rod	Lump sum	
Slnice No. 2 at R. L. 42·10.—		
Repairing the existing sluice	Lump sum	
Weir 50 ft. long at R. L. 50·00.—		
Petty repairs such as jelly wedging to apron and construction of a masonry toe wall.	Lump sum	
Extending the above weir by 50 ft.—		
1. Earthwork	C. yd.	16
2. Burnt brick in surki mortar	C. ft.	141
3. Plastering with surki mortar	Sq.	20·0
4. Burnt stone slabs 6" thick dressed	S. ft.	66
5. Rough stone apron	C. yd.	55

E. RAMASWAMY IYER,
For *Deputy Commissioner.*